

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-171-21151-00-00
Spot: SWSENE Sec/Twnshp/Rge: 28-16S-34W
1450 feet from S Section Line, 2280 feet from W Section Line
Lease Name: BLAKEY Well #: 2-28
County: SCOTT Total Vertical Depth: 4885 feet

Operator License No.: 7311
Op Name: SHAKESPEARE OIL CO., INC.
Address: 202 W MAIN ST
SALEM, IL 62881

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	264		WITH 185 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/12/2015 2:00 PM
Plug Co. License No.: 33935 Plug Co. Name: H. D. DRILLING, LLC
Proposal Rcvd. from: LOU TRESNER Company: H. D. DRILLING, LLC Phone: (785) 256-2419

Proposed Plugging Method: 1ST PLUG AT 2480' WITH 50 SX CMT. 2ND PLUG AT 1500' WITH 80 SX CMT. 3RD PLUG AT 725' WITH 50 SX CMT. 4TH PLUG AT 290' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: WADE KLAUS Witness Type: NONE
Date/Time Plugging Completed: 09/12/2015 4:00 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

1ST PLUG AT 2480' WITH 50 SX CMT. 2ND PLUG AT 1500' WITH 80 SX CMT. 3RD PLUG AT 725' WITH 50 SX CMT. 4TH PLUG AT 290' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed [Signature]

RECEIVED
SEP 14 2015
KCC DODGE CITY [Signature]

(TECHNICIAN)
Received
KANSAS CORPORATION COMMISSION

SEP 18 2015
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3