

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-22167-00-00
Spot: SWNESE Sec/Twnshp/Rge: 14-8S-17W
2970 feet from N Section Line, 330 feet from E Section Line
Lease Name: CHESNEY C Well #: 1
County: ROOKS Total Vertical Depth: 3395 feet

Operator License No.: 30911
Op Name: SNEATH, GENE DBA LUCKY IRON
Address: 2060 17 RD
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3395		150 SX
SURF	8.625	257		75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/04/2015 4:00 PM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: GENE SNEATH Company: LUCKY IRON OIL Phone: (785) 434-4807

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Production perforations at 3150' - 3155'.
Perforated at 1435' and 800'.
Casing leak at 1132' - 1135'

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/04/2015 6:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Operator ran 3 7/8" bit to 3000' with power swivel and mud pump. Ran tubing to 3000' and pumped 110 sx cement w/200 # hulls. Pulled tubing to 1500' and pumped 115 sx cement w/200 # hulls to circulate cement to surface. Pulled all tubing. Topped off 4 1/2" casing w/20 sx cement. Hooked to 8 5/8" x 4 1/2" annulus and pumped 10 sx cement. Shut in pressure 200 psi.

GPS: 39.35688N -099.17695W

Perfs:

Top	Bot	Thru	Comments
3376	3380		
3156	3160		
3150	3155		

Remarks: QUALITY OILWELL TICKET # 1619

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

SEP 15 2015

SEP 18 2015

CONSERVATION DIVISION
WICHITA, KS