

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-25879-00-00
Spot: S2SWNE Sec/Twnshp/Rge: 27-20S-23W
2990 feet from S Section Line, 1938 feet from E Section Line
Lease Name: MARHOFER Well #: 1-27
County: NESS Total Vertical Depth: 4480 feet

Operator License No.: 34876
Op Name: TRIPLE CROWN OPERATING LLC
Address: 2201 S. UTICA PL STE 100
TULSA, OK 74114

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4480	1476	WITH 145 SX CMT
SURF	8.625	249		WITH 175 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/09/2015 1:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DOYLE WILLIAMS Company: TRIPLE CROWN OPERATING Phone: (918) 518-5422

Proposed Plugging Method: SHOOT CASING OFF & PULL TO 1470' & PUMP 50 SX CMT. PULL CASING TO 700' & PUMP 80 SX CMT. PULL CASING TO 275' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/09/2015 7:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SHOT CASING OFF AT 1476' & PULLED ONE JOINT. 1ST PLUG AT 1430' WITH 50 SX CMT. 2ND PLUG AT 715' WITH 80 SX CMT. PULLED TO 280' & PUMPED 106 SX CMT. CMT CIRCULATED TO SURFACE. PULLED CASING & TOPPED OFF WITH 35 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4304	4312		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed Michael Maier

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

SEP 18 2015

CONSERVATION DIVISION
WICHITA, KS

RECEIVED
SEP 14 2015
KCC DODGE CITY