

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-23762-00-00
Spot: NWNW Sec/Twnshp/Rge: 20-34S-10W
4963 feet from S Section Line, 4880 feet from E Section Line
Lease Name: DAVIS Well #: 1-20
County: BARBER Total Vertical Depth: 5826 feet

Operator License No.: 5822
Op Name: VAL ENERGY, INC.
Address: 125 N MARKET ST STE 1710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4780		WITH 2 SX CMT
PROD	5.5	5375	3856	WITH 175 SX CMT
SURF	8.625	222		WITH 190 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/28/2015 8:00 AM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: DION HOWARD Company: VAL ENERGY, INC. Phone: (316) 263-6688

Proposed Plugging Method: CIBP @ 4780' WITH 2 SX CMT. PLUG AT 640' WITH 10 SX GEL & 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/28/2015 9:45 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4780' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 640' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 280' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4868	4880		
4846	4854		
4830	4880		

KCC WICHITA
SEP 14 2015
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
SEP - 8 2015
KCC DODGE CITY