

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-083-20252-00-00
Spot: SWSE Sec/Twnshp/Rge: 33-21S-24W
736 feet from S Section Line, 1869 feet from E Section Line
Lease Name: BINDLEY WF UNIT Well #: 204
County: HODGEMAN Total Vertical Depth: 4744 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT	5.5	1689		WITH 350 SX CMT
PROD	5.5	4741	0	WITH 250 SX CMT
SURF	8.625	609		WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/10/2015 12:00 PM
Plug Co. License No.: 32938 Plug Co. Name: NORTH FORK WELL SERVICE LLC
Proposal Rcvd. from: JOE RUPP Company: VESS OIL CORPORATION Phone: (785) 798-5151

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 35 SX CMT & 150# HULLS. PULL TBG TO 1700' & PUMP CMT & HULLS UNTIL IT CIRCULATES. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/10/2015 3:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4650' & PUMPED 50 SX CMT & 200# HULLS. PULLED CASING TO 1700' & PUMPED 180 SX CMT & 300# HULLS. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 25 SX CMT. TIED ONTO BACKSIDE & PUMPED 40 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4662	4666		
4621	4624		
4619	4622		

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Michael Maier
SM (TECHNICIAN)

RECEIVED
SEP 14 2015
KCC DODGE CITY MR

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

SEP 18 2015
CONSERVATION DIVISION
WICHITA, KS