

1 040934

2-8

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-01,011-01
C NE SW, SEC. 7, T 29 S, R 14 W/EX
1980 feet from S section line
3300 feet from E section line
Lease Name Stelzer Well # 1 OWWO
County Pratt 151.45
Well Total Depth 4660 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 311

TECHNICIAN'S PLUGGING REPORT
Operator License # 5663
Operator: Hess Oil Company
Name & Address P.O. Box 1009
McPherson, KS 67460

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9 a.m. Day: 7 Month: 2 Year: 19 95

Plugging proposal received from Jeff Clarke

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4652' w/150 sx cement, PBTD 4600', Perfs at 4554-62, 4547-49'

1st plug sand back to 4430' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 100 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:45 a.m. Day: 8 Month: 2 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 4430' and dumped 5 sx cement on top of sand
bridge through bailer, 2/7/95-2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls,

10 sx gel, and 25 sx cement at 200#-Hole in surface pipe-fluid and gel came up backside of
8 5/8". Allied pumped water down 8 5/8" surface pipe to attempt to clear hole of cement.

Shut down and waited on rig to run tubing. 2/8/95-Pratt Well Service rigged up on well. Ran
tubing and bit in hole. Never tagged any cement. Ran tubing in to 900'. Loaded hole with

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2375' of 5 1/2" casing. gel. (see back)

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-22-95

INV. NO. 42251

Handwritten notes: RWD 02-22-95

Signed [Signature] (TECHNICIAN)

PLUGGING REPORT:

3rd plug at 900' with 50 sx cement,

4th plug at 322' with 50 sx cement,

5th plug at 40' with 10 sx cement.

0310781

STAD
200 1520'