

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NW SE NW , Sec. 2 , T 29 S, R 14 W/X
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,411-80-00

1650 feet from N/X section line

1650 feet from W/X section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5020

Lease Name Omo Well # 1-2

Operator: Rine Exploration Company
Name & 300 W. Douglas, Suite 645
Address Wichita, KS 67202

County Pratt

Well Total Depth 4685 feet 152.26

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1155

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Beredco License Number 5147

Address 401 East Douglas, Suite 402, Wichita, KS 67202

Company to plug at: Hour: 6:30 am Day: 12 Month: February Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Gary Marshal

(company name) Beredco (phone) 316-265-2856

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 1200' with 50 sx cement

2nd plug at 600' with 25 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 10 sx cement, 6th plug to circulate mousehole
with 10 sx cement. Plug water well with 5 sx cement.

Signed Steve A. Bennett
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8:30 am Day: 12 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1200' with 50 sx cement, 2nd plug at 600' with
25 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to
surface with 10 sx cement, 5th & 6th plugs to circulate rathole and mousehole with
10 sx cement each. Plug water well with 5 sx cement.

Remarks: Use 60/40 Pozmix with 2% gel 3% cc. by Bouie

RECEIVED
STATE CORPORATION COMMISSION
FEB 15 1984
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / did not) observe this plugging.

Signed Steve A. Bennett
(TECHNICIAN)

INVOICED

DATE 2-23-84

WV. NO. 0353-

2-12