

Y KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1964
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Mull Drilling Co. Inc.

Complete Address: 1625 Wichita Plaza. Wichita, Kansas

Lease Name Trimpa Well No. # 1

Location C SW SW Sec. 9 Twp. 27 Rge. (E) (W) 21

County Ford Total Depth 5062'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Co.

Address: Great Bend, Kansas License No. 49

Operation Completed: Hour 8 PM Day 14 Month 7 Year 64

The Above well was plugged as follows:

8 5/8"-293' Circulated w/cement. 4 1/2"-5062' Cemented. Top perforations 4928'

Plug bottom w/20 Sax. cement top cement 4500'. Mud 4500' to 700'

Spotted 25 Sax. cement 700' to 625' Mud 625' to 290'

Spotted 25 Sax. cement 290' to 215' Mud 215' to 45'

Plug, 15" ax. cement 45' to 0. Pulled 2000' 4 1/2" pipe.

Cut pipe off 5' below ground level. Weld plate on pipe.

Company Pump.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *[Signature]*
Well Plugging Supervisor

DATE 7/16/64
INV. NO. 9489-W