

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

API #: 15-057-20,092-0000

Operator's Full Name Imperial Oil Co.

Complete Address 720 Fourth Financial Center, Wichita, Kansas

Lease Name Madison Well No. 1

Location C SW SW Sec. 21 Twp. 27 Rge. (E) (W) 21

County Ford Total Depth 5035'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Slawson Drlg.

Address Wichita, Kansas License No.       

Operation Completed: Hour 7 A Day '23 Month 9 Year 1976

The above well was plugged as follows:

RTD 5035' 8 5/8 csg set 403' cwc 175 sx. Plg. Mat. 50-50 poz.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 500' thru drill pipe.

Heavy mud to 300' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

      

      

      

      

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey  
Well Plugging Supervisor

DATE 9/29/76  
INV. NO. 3875-W