

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SW NE SW

SEC. 35 TWP. 27 RGE. 21

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Birney

Operator Panhandle Eastern Pipe Line Co. P.O. Box 979, Liberal, Kansas

Field \_\_\_\_\_ County Ford

Total Depth 5015 Feet.

(Describe briefly the manner in which the well was plugged)

- 329' of 8 5/8 casing in hole, none pulled out
- 5015' of 5 1/2 casing in hole, 2555' pulled out. Cement 5015' to 4910'.
- 4910' to 1500' Heavy drilling mud
- 1500' to 1408' Cement plug
- 1408' to 300' Heavy Drilling mud
- 300' to 266' Cement plug
- 266' to 42' Heavy drilling mud and sand
- 42' to 8' Cement plug.
- The surface pipe cut off at bottom of cellar and cellar leveled with ground.

**PLUGGING**  
FILE SEC. 35 TWP. 27 R. 21  
BOOK PAGE 49 LINE 9

RECEIVED  
STATE CORPORATION COMMISSION

OCT 10 1952

CONSERVATION DIVISION  
Wichita, Kansas

10-18-52

R. J. Phillippe  
District Conservation Agent

Date October 5, 1952.