

15-173-01539-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

OR  
FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

Sedgwich County. Sec. 12 Twp. 26 Rge. 1 (E) (W)

NORTH


Locate well correctly on above  
Section Plat

Location as "NE1/4NW1/4SW1/4" or footage from lines.....  
 Lease Owner: Prunty Production Co.  
 Lease Name: A. W. Wright Well No. 2  
 Office Address: Ponca City Okla.  
 Character of Well (completed as Oil, Gas or Dry Hole): Oil  
 Date well completed: Jan. 1943.  
 Application for plugging filed: April 2 1946  
 Application for plugging approved: " 2 1946  
 Plugging commenced: " 10 1946  
 Plugging completed: " 18 1946  
 Reason for abandonment of well or producing formation: 99% Water

If a producing well is abandoned, date of last production: Dec 1945  
 Was permission obtained from the Conservation Division or its agents before plugging was com-  
 menced? Yes

Name of Conservation Agent who supervised plugging of this well: John Roberts  
 Producing formation: Viola Dolomite Depth to top: 3326 Bottom: 3328 Total Depth of Well: 3328 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
10" Surface	Pipe				154.9'	0
5 1/2" Oil	"				3326'	2316'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from..... feet to..... feet for each plug set.  
5 Sacks Cement dumped with bailer at 3328' Filled to 3283' filled with sand to 3030' Ripped Pipe and tested  
5sacks cement dumped with bailer filled to 2985' filled with sand to 2630' Ripped pipe and tested  
3sacks cement dumped filled to 2603' filled with mud to 160' 15 Sacks filled to 130' mud to 10' 5sacks cement filled to surface.

**PLUGGING**  
 FILE 15-173-01539-0000  
 BOOK PAGE 55 LINE 37

STATE CORPORATION COMMISSION  
 MAY 25 1946

(If additional description is necessary, use BACK of this sheet)  
 Correspondence regarding this well should be addressed to: Prunty Production Co., Ponca City Okla.  
 Address.....

STATE OF Kansas, COUNTY OF Sedgwich, ss.  
J. W. Walker (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. W. Walker

(Address) May 25 1946  
Notary Public

SUBSCRIBED AND SWORN to before me this 7th day of May, 1946

My Commission Expires June 10, 1946

Owner & Operator: Prunty Production Company  
 Lease & Well: A. W. Wright No. 2  
 Location: NE/4 NW/4 SW/4 Section 12-26S-1W, Sedgwick County, Kansas  
 Commenced: November 28, 1942  
 Completed: December 15, 1942  
 Casing: 152' of 10 3/4"  
 3344' 10" of 5 1/2"

L O G

Sand & Gravel	65
Shale	140
Shale & Shells	314
Broken Lime	414
Shale & Shells	1184
Shale	1550
Shale & Shells	1743
Lime	1783
Broken Lime	1839
Shale & Shells	2175
Shale	2205
Broken Lime	2249
Shale	2270
Lime	2302
Shale	2352
Lime	2506
Broken Lime	2583
Lime, soft	2683
Lime	2747
Shale & Shells	2838
Broken Lime	2940
Shale	3084
Chat	3048
Lime	3242
Shale	3326
Viola Dolomite	3328

Set 152' of 10 3/4" OD Casing @159' and cemented with 125 sacks cement.

Set 3344' 10" of 5 1/2" OD 14# Casing at 3326' and cemented with 250 sacks cement.

Production 1st 24 hours - 45 Bbls. Oil and 675 Bbls. water.

**PLUGGING**  
 FILE SEC LYT 76R/W  
 BOOK PAGE 55 LINE 37

