


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

Kiowa County, Sec. 15 Twp. 27 Rge. 20 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE SE
Lease Owner Beardmore Drilling Company
Lease Name Fralick Well No. 1
Office Address 827 Beacon Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4-30 19 62
Application for plugging filed 4-30 19 62
Application for plugging approved 4-30 19 62
Plugging commenced 4-30 19 62
Plugging completed 4-30 19 62
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4938 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand		0	170'			
		170'	359'	8 5/8"	359'	0
Clay						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

0' to 40'	-	10 sacks cement
40'	-	wood plug
40' to 225'	-	heavy mud
225' to 300'	-	25 sacks cement
300'	-	wood plug
300' to 4938'	-	heavy mud

RECEIVED
STATE CORPORATION COMMISSION
MAY 7 1962
CONSERVATION DIVISION
Wichita, Kansas

Also: 2 sacks cement in rat hole

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Gabbert-Jones Drilling Company, Inc.
Address 5-4 Orpheum Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Heber Beardmore (Signature of Contractor)

(Signature of Owner or Operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
827 Beacon Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of May, 19 62

My commission expires 7-13-63

Shirley Ann Jackson
Shirley Ann Jackson
Notary Public.

GABBERT-JONES DRILLING CO., INC.
WICHITA, KANSAS
DRILLERS WELL LOG

FRALICK #1
 C NE SE SECTION 15-27S-20W
 KIOWA COUNTY, KANSAS


COMMENCED: APRIL 16, 1962
 COMPLETED: APRIL 30, 1962

OPERATOR - BEARDMORE DRILLING COMPANY.

DEPTH		FORMATION	REMARKS
FROM	TO		
0	170	SAND	
170	359	CLAY & SHALE	RAN 17 JTB. 8-5/8" CASING (367') SET @ 359' W/225 SACKS CEMENT
359	650	SHALE	
650	735	SAND & SHALE	
735	760	LIME	
760	856	SHALE & SHELLS	
856	1290	RED BED & SHALE	
1290	1340	SHELLS & ANHYDRITE	
1340	1385	SHALE	
1385	1735	SHALE & SHELLS	
1735	1800	LIME & SHALE	
1800	1990	SHALE	
1990	2340	SHALE & SHELLS	
2340	2370	LIME & SHALE	
2370	2895	LIME	
2895	4085	LIME & SHALE	
4085	4855	LIME	
4855	4881	LIME, CHERT & SHALE	
4881	4934	LIME	
4934	4938	LIME & CHERT	
4938	TD		DRY & ABANDONED

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 7 1962
 CONSERVATION DIVISION
 Wichita, Kansas

I, E. E. HALL, CERTIFY THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG FOR THE WELL DRILLED IN C NE SE SECTION 15-27S-20W, KIOWA COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.




 E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 3RD DAY OF MAY, 1962, PERSONALLY APPEARED E. E. HALL TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

MY COMMISSION EXPIRES OCTOBER 2, 1963



 VIRA A. MCKENZIE, NOTARY PUBLIC.