

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Ford County, Sec. 32 Twp. 27 Rge. 21 (E) W (W)

NORTH

Locate well correctly on above
Section Plat

Location as "NE/CNWxSWx" or footage from lines _____
 Lease Owner Toto Gas Company
 Lease Name Wagler Well No. 1
 Office Address First Nat'l. Bank Bldg., Oklahoma City, Okla.
 Character of Well (completed as Oil, Gas or Dry Hole) D & A
 Date well completed May 5 19 61
 Application for plugging filed May 5 19 61
 Application for plugging approved May 5 19 61
 Plugging commenced May 5 19 61
 Plugging completed May 5 19 61
 Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production _____ 19 _____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	556.51'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with heavy mud to 530' with 1/2 sx hulls.
Set bottom plug @ 530' with 20 sx cement. Set top
plug @ 35' with 1/2 sx hulls and 10 sx cement.

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 11 1961 5-11-61
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Red Tiger Drilling Company
 Address Box 173, Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
George A. Angle (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Angle
580 Fourth Nat'l. Bank Bldg., Wichita
 (Address)

SUBSCRIBED AND SWORN to before me this 8th day of May, 19 61

My commission expires 11-17-62 Madame Skad Notary Public.



DRILLERS LOG

No. 1 Wagler

CASING RECORD: 8 5/8" @ 556.51' w/350 sx cement
 COMPANY: Toto Gas Company
 CONTRACTOR: Red Tiger Drilling Company
 COMMENCED: April 19, 1961
 COMPLETED: May 5, 1961
 DESCRIPTION: SW SW 32-27S-21W Ford County, Kansas
 ELEVATION:
 TOTAL DEPTH: 5040'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand & Gravel	0	15	
Sandy Clay	15	80	
Shale & Shells	80	455	
Shale & Sand	455	505	
Shale & Shells	505	535	
Lime	535	563	
Shale	563	940	
Shale, Red Rock, Gyp Shells	940	1336	
Anhydrite	1336	1372	
Shale & Shells	1372	1730	
Shale	1730	1975	
Shale & Shells	1975	2130	
Lime Shale	2130	2445	
Lime	2445	2685	
Shale & Lime	2685	3930	
Lime	3930	4060	
Lime & Shale	4060	4290	
Lime	4290	4670	
Lime & Shale	4670	4760	
Lime	4760	4925	
Chirty Lime	4925	5000	
Lime	5000	5040	

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 11 1961
 CONSERVATION DIVISION
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

George A. Angle

 George A. Angle

Subscribed and sworn to before me this 8th day of May, 1961.

Meynie Head

 Notary Public

My Commission Expires:

11-17-62