

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Ford SEC. 35 TWP. 27S RGE. 21W ~~E/W~~
Location as in quarters or footage from lines:
660' FSL & 1320' FEL

Lease Owner Texas Oil and Gas Corporation
Lease Name Birney "E" Well No. 1
Office Address 200 W. Douglas-Suite 300, Wichita, KS 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed August 24, 1981
Application for plugging filed Verbal application
Plugging commenced August 24, 1981
Plugging completed August 24, 1981
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas

Producing formation _____ Depth to top _____ bottom T.D. 5050'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	562'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

850' - 75 sxs
500' - 40 sxs + 1/2 sk Hulls + SWBP
40' - 10 sxs
RH - 5 sxs
MH - 5 sxs

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Dowell Div., Dow Chemical Co.
Hwy. 281 & Santa Fe, Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Sedgwick, ss.

Gary Younger, Agent (~~employee~~ of owner) or (~~owner~~) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) [Signature]
251 N. Water, #10, Wichita, Ks.
(Address) 67202

SUBSCRIBED AND SWORN TO before me this 1st day of September, 19 81

Elsie Willison
Elsie Willison - Notary Public.

My Commission expires: July 25, 1982

RECEIVED
STATE CORPORATION COMMISSION

SEP - 3 1981

CONSERVATION DIVISION
Wichita, Kansas

KANSAS DRILLERS LOG

COMPANY Texas Oil & Gas Corp.

SEC. 35 T. 27S R. 21W

FARM Birney "E" NO. 1

LOC. 660' FSL & 1320' FEL

COUNTY Ford

ROTARY TOTAL DEPTH 5,050'

COMM. August 13, 1981

COMP. August 24, 1981

CONTRACTOR H-30, INC. (Rig #3)

ISSUED September 1, 1981

CASING

10 3/4"

8 5/8" Set at 562' cemented w/450 sxs cement

5 1/2"

4 1/2"

ELEVATION 2,353' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Red Bed	565'
Red Bed and Shale	1,599'
Shale and Lime	2,300'
Lime and Shale	2,500'
Shale and Lime	2,715'
Lime and Shale	5,050'
Rotary Total Depth	5,050'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.


H-30, INC.

Gary Younger
Gary Younger

State of Kansas)
) ss:
County of Sedgwick)

Subscribed and Sworn to before me a Notary Public in and for said county and state this 1st day of September, 1981.

Elsie Willison
Elsie Willison - Notary Public



My Commission Expires:
July 25, 1982

RECEIVED
STATE CORPORATION COMMISSION
SEP - 3 1981
CONSERVATION DIVISION
Wichita, Kansas