


STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above Section Flat

For d _____ County. Sec. 34 Twp. 27 Rge. 21W (E) _____ (W) _____
Location as "NE/CNW&SW" or footage from lines G SW NW
Lease Owner Halliburton Oil Producing Co.
Lease Name Weaver Jones #1 Well No. _____
Office Address Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 11/25/74 _____ 19____
Plugging completed 12/17/74 _____ 19____
Reason for abandonment of well or producing formation depleted.
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Thomas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4952 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	567	none
				5 1/2"	4951' to 3012'	3012'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4952', ran sand to 4900' and ran 5 sacks cement. Loaded hole with water, shot pipe at 4007', 3595', spotted 40 barrels oil and pumped plug to 3500' at 300 lb. pressure. Checked hole to 3192', pushed plug to 3550' and shot pipe at 3501', 3405', 3310', 3220', 3123', 3010', pulled 95 joints. Mixed 3 sacks gel, 1 sack hulls, 50 sacks cement, 17 sacks gel, 2 sacks hulls and 50 sacks cement, plug at 900', 35 sacks cement, plug at 520'. Mixed 2 sacks gel, 15 sacks cement at 40', 500 p.s.i.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE ss. NOEL J. KNIGHT

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Noel Knight*
CHASE, KANSAS
(Address)

Subscribed and sworn to before me this 31st day of December, 19 74

Margaret Melcher
Notary Public.

My commission expires _____
MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

RECEIVED
STATE CORPORATION COMMISSION

3 1975 1-3-75

CONSERVATION DIVISION
Wichita, Kansas

DECEMBER

JAN 01 1975

HALLIBURTON OIL PRODUCING CO.
COMP. CHECKED _____

DRILLER'S LOG

COMPANY: Halliburton Oil Producing Co., 117 Cameron Bldg., Okla. City, Okla. 73106
 CONTRACTOR: Hellar Drilling Company, Inc., Wichita, Kansas 67202
 LEASE: #1 Weaver-Jones
 LOCATION: c SW NW 34-27S-21W, Ford County, Kansas
 COMMENCED: November 21, 1971
 COMPLETED: December 4, 1971
 CASING: Set 8 5/8" Surface Casing @ 567'w/450 sacks cement
 Set 5 1/2" Casing @ 4951'w/100 sacks cement

0-561	, Shale - Sand
561-569	Blaine-Anhydrite
569-1328	Shale & Shells
1328-1359	Anhydrite
1359-1780	Shale & Red Bed & Shells
1780-2130	Shale & Salt Section
2130-2655	Salt Section
2655-2970	Lime
2970-3725	Lime & Shale
3725-3895	Lime & Shale (Topeka Section)
3895-4240	Lime & Shale
4240-4380	Lime & Shale - Brown Lime
4380-4918	Lime
4918-4952	Cong.-Miss.
4952	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 21 1974
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Weaver-Jones, located in c SW NW 34-27S-21W, Ford County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

By D. L. Hellar
 President - D. L. Hellar

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 8th day of December, 1971.

My Commission Expires: March 25, 1972.

Catherine Darcey
 Notary Public - Catherine Darcey

3.05/ft

9 16,522.54

