

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-057-20403-0000

API NUMBER 057-2C403C20403

LEASE NAME Pinkney

WELL NUMBER 1

330' Ft. from S Section Line

330' Ft. from E Section Line

SEC. 26 TWP. 27 RGE. 23 ~~XXXX~~(W)

COUNTY Ford

Date Well Completed _____

Plugging Commenced 08/19/85

Plugging Completed 08/19/85

LEASE OPERATOR Mitchell Energy Corp.

ADDRESS P. O. Box 4000, The Woodlands, Texas 77387-4000

PHONE#(713) 363-5818 OPERATORS LICENSE NO. _____

Character of Well Dry Hole

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Dry Hole Depth to Top -- Bottom -- T.D. --

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Mississippi	Salt Water	5112	5114	8-5/8"	615'	0'
Mississippi	Salt Water	5022	5038	4-1/2"	5349'	2316'
Morrow	Salt Water	5012	5014			
Cherokee	Salt Water	4988	4990			
Neva	Salt Water	3189	3195			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

CIBP at 5100' KB. CIBP at 4950'. CIBP at 3175' KB with 2 sacks cement. Cut casing at 2316'. Circulated hole full of 9.5 ppg mud. Cement plug at 650' KB - 100 sacks 60/40 Class "H" - Pozmix - Cement top 300'. Cement plug at surface - 10 sacks, 60/40 Class "H" - Pozmix. 1/2" steel plate welded on surface casing 3' below ground level.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. _____

Address P. O. Box 963, Pratt, Kansas 67124

STATE OF Texas COUNTY OF Tarrant, ss.

George R. Jackson (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) George R. Jackson George R. Jackson

(Address) P.O. Box 2922, Ft. Worth, TX 76113

SUBSCRIBED AND SWORN TO before me this 8th day of October, 19 85

Dorothy Clark Notary Public

My Commission Expires March 14, 1989
STATE CORPORATION COMMISSION

OCT 21 1985 10-21-85

Form CP-4
Revised 08-84