


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Ford County, Sec. 3 Twp. 27-S Rge. 23-W (E) (W)
Location as "NE/CNW/SW" or footage from lines. SW SW NE
Lease Owner Apache Oil Corporation
Lease Name A. W. Gum Well No. 1
Office Address 823 South Detroit, Tulsa 20, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 27 19 59
Application for plugging filed November 27 19 59
Application for plugging approved November 27 19 59
Plugging commenced November 27 19 59
Plugging completed November 27 19 59
Reason for abandonment of well or producing formation no oil or gas found in commercial quantities
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill LacKamp, Stafford, Ks.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5182 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	491'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with extra heavy rotary mud from total depth to 450'. Set Bridge Plug and 20 sacks at 450'. Filled hole with extra heavy rotary mud from Plug #1 to 35'. Bridge Plug and 10 sacks cement to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION

1-6-60 JAN 6 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Capitt Drilling, Inc.
Address 814 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
R. R. McNicol (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. R. McNicol
814 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of December, 19 59

My commission expires Sept. 30, 1963
Darlene May Notary Public.

ROTARY DRILLING LOG

OPERATOR: Apache Oil Corporation
 A. W. Gum No. 1 ✓
 SW SW NE 3-27S-23W,
 Ford County, Kansas

CONTRACTOR: Capitt Drilling, Inc.
 COMM: 10-28-59
 COMP: 11-27-59

R

Formations:

Remarks: Set 8-5/8" surface casing
 at 491' cemented with 350
 sacks Pozmix, w/2% C.C. &
 6% Strata Crete

Sandy Clay	80'
Sand	95'
Shale & Lime Streaks	491'
Shale & shells	1500'
Shell & Shale	1643'
Shale & Lime Streaks	1835'
Shale & Shells	2292'
Shale w/Lime Streaks	2425'
Lime	3945'
Lime & Chalk	3982'
Lime	4150'
Lime & Chalk	4214'
Lime & Chalk Streaks	4237'
Lime	5182'
Rotary Total Depth (D&A)	5182'

We certify the above log is true and
 correct to the best of our knowledge
 and belief.

CAPITT DRILLING, INC.

R. R. McNicol

R. R. McNicol

RECEIVED
 STATE COMMISSION
 AUG 4 1960
 CONSERVATION DIVISION
 Kansas