

KANSAS

Form CP-3
Rev. 6-4-68

14
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-155-00180-0000

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Woodman & Iannitti Oil Company

Complete Address 706 Union Nat'l Bldg., Wichita, Kansas 67202

Lease Name Longsdorf Well No. 1

Location NE NW SW Sec. 29 Twp. 26 Rge. 4 (E) (W) X

County Reno Total Depth 4220'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D & A _____

Other well as hereafter indicated (Gas zone broke into well--pressured up)

Plugging Contractor Operator and Haliburton Oil Well Cementing Co.

Address _____ License No. _____

Operation Completed: Hour 3 PM Day 9 Month October Year 1969

The above well was plugged as follows:

10/7/69 Pumped 20 sacks gel-mud with hulls and 200 sacks cement with 6% gel and 2% calcium chloride.

10/8/69 Pumped 100 sacks common cement with 3% HA-5--killed pressure on 5 1/2" casing.

10/9/69 Pumped 30 sacks cement into annulus at 600 psi.

10/9/69 Pumped 30 sacks into 5 1/2" casing through 2" tubing.

Well completley dead and standing full of cement.

I hereby certify that the above well was plugged as herein stated.

Signed: *J. Thomas*
Well Plugging Supervisor

INVOICED

DATE 10/15/69

INV. NO. 653-w