

15-095-00466-00-00

Form CP-3
Rev. 6-26-62

MP
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

DEC 20 1965

Operator's Full Name Leben Drilling, Inc.

Complete Address: P. O. Box 486, Great Bend, Kansas

Lease Name Simmons Well No. # 1

Location SW SE ~~SW~~ 10W ¹⁰⁰⁰ Sec. 1 Twp. 28 Rge. 5 (E) (W) W

County Kingman Total Depth 3830'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 2:30 PM Day 18th Month Dec. Year 1965

The Above well was plugged as follows:

212' of 8 5/8" surface pipe, cemented with 175 sacks. 3803' of 2 1/2" tubing,
cemented with 250 sacks. 1884' of 5 1/2" long string, cemented with 140 sacks.
Plug back to 3803'. Top perferation in 2 1/2" tubing 3666', 10 sacks of cement
into tubing to squeeze all perferations(pumped). 2500' of 2 1/2" tubing was re-
covered from the hole. All perferations in 5 1/2" had been squeezed. 5 sacks of
cement was pumped in 5 1/2" to 1550'. 700' of 5 1/2" casing was recovered from the
hole. Hole was filled with mud to 200', rock bridge from 200' to 190', and
cemented with 25 sacks. Hole was filled with mud to 40', rock bridge from 40'
to 30', and cemented with 10 sacks to the base of the cellar.
I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 12/20/65

INV. NO. 2431-W