

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
10-24-78  
OCT 24 1978

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - -

CONSERVATION DIVISION  
Wichita, Kansas (of this well)

Operator's Full Name Felso Casing Pulling

Complete Address Box 176 - Chase Farm, 67524

Lease Name Neelley Well No. 1

Location SW-SW-SW- Sec. 1 Twp. 26 Rge. 15 (E) (W) X

County Pratt Total Depth 4365

Abandoned Oil Well X Gas Well [ ] Input Well     SWD Well     D & A    

Other well as hereafter indicated    

Plugging Contractor Co. Traylor

Address     License No. 683

Operation Completed: Hour 7:45 Am Day 23 Month 10 Year 1978

The above well was plugged as follows:

517' - 8 5/8" Casing - 5 1/2" Casing set @ 4160' w/ 120 saf cement  
Safe plug 3860' - push plug to 3775' sand back to 3750'  
tapped sand w/ 5 saf mixed Cement w/ dump bailer  
pull 2255' - 5 1/2" Casing - Allied mixed & pumped 3 saf  
pull 20 saf gel release plug mixed & pumped 150  
saf 60/40 pos-27 bal-37cc to top of Casing

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 10-25-78  
INV. NO. 8383.0