

15-155-20931-0000

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Reno SEC. 21 TWP. 26 RGE. 4 K/W  
 Location as in quarters or footage from lines:  
NW NW NE


Locate Well  
 correctly on above  
 Section Plat.

Lease Owner Raymond Oil Company, Inc.  
 Lease Name SEIDL Well No. 1  
 Office Address One Main Place, Suite 900 Wichita, KS 67202  
 Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
 Date Well Completed 4-22-83  
 Application for plugging filed 4-22-83  
 Plugging commenced 4-22-83  
 Plugging completed 4-22-83  
 Reason for abandonment of well or producing formation \_\_\_\_\_

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Glen Ward  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4125

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Bottom Plug: @ 260' w/35 sacks 50/50 pozmix, 2% gel 3% cc. thru drill Pipe  
 Top Plug: @ 60' w/20 sacks " " " " " " "  
10 sacks in Rat Hole

(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor Duke Drilling Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.  
Bill Draney (employee of owner) or ~~owner or operator~~ of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) Bill Draney  
Box 823 Great Bend, KS 67530  
 (Address)

SUBSCRIBED AND SWORN TO before me this 25 day of April, 1983

Dorothy M. Hague  
 Notary Public.

My Commission expires: 4-29-86

RECEIVED  
 STATE CORPORATION COMMISSION

APR 26 1983

CONSERVATION DIVISION  
 Wichita, Kansas

DRILLERS' WELL LOG

DATE COMMENCED: April 12, 1983  
DATE COMPLETED: April 22, 1983

Raymond Oil Company, Inc.  
SEIDL #1  
NW-NW-NE  
Sec. 21, T26S, R4W  
Reno County, Ks.

ELEVATION: 1505 K.B.

0 - 2257' Surface Soil, Red Bed, Shale  
2257 - 2629' Lime  
2629 - 2633' Shale  
2633 - 2871' Lime & Shale  
2871 - 3354' Lime  
3354 - 3380' Shale  
3380 - 3500' Lime, Shale, Chert  
3500 - 3680' Sand  
3680 - 3977' Chert & Lime  
3977 - 4049' Shale  
4049 - 4088' Sand  
4088 - 4125' Chert  
4125' RTD

FORMATION DATA

Topeka 2257'  
Heebner 2629'  
Br. Lime 2833'  
Lansing 2871'  
Base K.C. 3354'  
Marmaton 3380'  
Cheokee 3500'  
Mississippi 3680'  
Kinderhook 3977'  
Misener 4049'  
Viola 4088'  
RTD 4125'

Surface Pipe: Set new 8-5/8",  
20# @206' w/150 sacks cement  
2% gel 3% cc.

AFFIDAVIT

STATE OF KANSAS  
COUNTY OF BARTON) ss

Bill Draney of lawful age, does swear and state that the facts and  
statements herein are true and correct to the best of his knowledge.

Bill Draney

Subscribed and sworn to before me this 25 day of April 1983.

My Comm. Expires:

4-29-86

Deborah M. Hague  
Notary Public

RECORDED  
STATE CORPORATE COMMISSION

APR 26 1983

CONSERVATION DIVISION  
Wichita, Kansas