


15-155-01008-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Reno County, Sec. 21 Twp. 26S Rge. (E) 4 (W)  
Location as "NE/CNW/SW" or footage from lines. NE NE SE  
Lease Owner Thunderbird Drilling, Inc.  
Lease Name Meyer Well No. 1  
Office Address 712 Union Center, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 10 1958  
Application for plugging filed October 10 19 58  
Application for plugging approved October 10 19 58  
Plugging commenced October 10 19 58  
Plugging completed October 10 19 58  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Fred Hampel, Pretty Prairie, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4080 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	200'	8 5/8"	202.16	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set plug at 180' with 1/3 sack hulls. Mixed and poured 20 sacks of cement. Filled hole with mud to 40', set plug and 1/3 sack hulls. Mixed and poured 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Thunderbird Drilling, Inc.  
Address 712 Union Center, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK  
Charles W. Aikins, Jr. (operator of well) owner or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
712 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of October 19 58

My commission expires Sept. 5, 1960

Jenell Scharz RECEIVED  
STATE CORPORATION COMMISSION  
Wichita, Kansas

PLUGGING  
FILE SEC 21 T. 26 R. 4W  
BOOK PAGE 137 LINE 8

OCT 17 1958 10-17-58

CONSERVATION DIVISION  
Wichita, Kansas

THUNDERBIRD DRILLING, INC

#1 MEYER WELL LOG

15-55-01008-0000

LOCATION: NE NE SE Sec. 21,  
Twp. 26S, Rge. 4W  
Reno County, Kansas

CONTRACTOR: Thunderbird Drilling, Inc.  
712 Union Center  
Wichita, Kansas

SURFACE CASING: 8 5/8" set at 200' with 140 sacks  
of cement, 1% gel and 2 sacks Calcium  
Chloride.

OIL STRING: None

ELEVATION: 1489' K. B.  
1486' D. F.  
1484' G. L.

COMMENCED: September 20, 1958

COMPLETED: October 9, 1958

WELL LOG

0 - 60	Clay & Rock
60 - 960	Shale & Shells
960 - 1700	Shale & Lime
1700 - 1975	Shale & Shells
1975 - 2852	Shale & Lime
2852 - 3325	Lime
3325 - 3641	Shale & Lime
3641 - 3890	Cherty Lime
3890 - 3923	Shale & Lime
3923 - 3945	Lime
3945 - 4042	Shale & Lime
4042 - 4057	Shale & Sand
4057 - 4061	Viola Lime
4061 - 4075	Lime
4075 - 4080	Sand
4080	Rotary Total Depth

The undersigned, Charles W. Aikins, Jr., an officer of Thunderbird Drilling, Inc., hereby certifies that the above is a true and correct log of the formations encountered in the drilling of the #1 Meyer as shown in the daily drilling reports.

THUNDERBIRD DRILLING, INC.

*Charles W. Aikins, Jr.*  
Charles W. Aikins, Jr., Pres.

Subscribed and sworn to before me this 16th day of October, 1958.

My commission expires:  
September 5, 1960.

*Jenell Schartz*  
Jenell Schartz - Notary Public

RECORDED  
STATE CORPORATION COMMISSION

OCT 27 1958

PLUGGING  
FILE SEC. 21 T 26 R 4W  
BOOK PAGE 137 LINE 8

CONSERVATION DIVISION  
Wichita, Kansas