


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Reno County, Sec. 2 Twp. 26 Rge. 6 (E) E (W)
Location as "NE/CNW/SW" or footage from lines SE Corner Lot #3
Lease Owner Trans Era Petroleum, Inc.
Lease Name Schrag Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 4/27/53 19
Application for plugging filed 4/26/53 19
Application for plugging approved 4/26/53 19
Plugging commenced 4/27/53 19
Plugging completed 4/27/53 19
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation Depth to top Bottom Total Depth of Well 4135 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	215	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PLUGGING RECORD

Lay down drill pipe. Plugged hole, fir plug set at 215' with 15 sacks of cement mixed and run through drill pipe. Second plug was set at 20' with 5 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor
Address

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
Herbert R. Michaelis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Herbert R. Michaelis
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of May, 1953

My commission expires 1-30-57

24-7368-5 3-53-20M



Margie Cooper
RECEIVED
STATE CORPORATION COMMISSION
Notary Public.

5-7-53

MAY - 7 1953
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILED 5/7 2 1953
BOOK PAGE 98

Trans Era Petroleum, Inc.
Schrag #1

SE Corner, Lot #3 2-26-6
Reno County, Kansas

Total Depth: 4135'
Comm. 4/6/53
Comp. 4/27/53

15-155-00152-0000

Casing

8 5/8" Set @ 215'

Cement

150 sacks Pozmix

Formation	Depth
Shale-sand	20
Shale-shells	70
Sand-shale	105
Shale-shells	780
Anhydrite	810
Lime-shells-shale	970
Lime-shale	1415
Lime-shells-shale	1615
Lime-shale	1675
Shale	1860
Shale-lime	1980
Shale-lime-shells	2140
Shale-lime	2425
Lime	2740
Lime-shale	2743
Sandy lime	2834
Shale	2854
K.C. Lime	2890
Lime	3308
Lime-shale	3573
Shale	3579
Mississippi Lime	3615
Shale-chert	3671
Lime-chert	3712
Lime	3717
Mississippi Lime	3750
Lime-chert	3763
Lime	3815
Shale	3952
Sandy shale	3985
Viola Lime	3992
Lime	4005
Sand	4031
Lime-sand	4057
Simpson sand (hard)	4062
Sand	4109
Arbuckle Lime	4135'

STATE OF KANSAS)
) ss
RUSSELL COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.

Cons. Butz

Subscribed and sworn to before me this 29th day of April, 1953.

Margie Cooper

Notary Public

My commission expires: 1-30-57.

EXPIRES
MAY - 7
INSERV
WIL

PLUGGING
FRI SEC 3 T 26 R 64
BOOK PAGE 98 LINE 33