

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15.151-20206-00-00

API NUMBER 1-8-85

LEASE NAME THOMPSON

WELL NUMBER SWD #1

 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 1 TWP. 26 RGE. 15 ~~EX~~or(W)

COUNTY PRATT

Date Well Completed 1-8-85

Plugging Commenced 5-22-91

Plugging Completed 5-24-91

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR PRATT WELL SERVICE, INC.

ADDRESS P O BOX 847 PRATT, KANSAS 67124

PHONE#(316) 672-2531 OPERATORS LICENSE NO. 5893

Character of Well SWD oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on MAY 24, 1991 (date)

by DUANE RANKIN (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached?

Producing Formation NONE Depth to Top Bottom T.D. 4165

Show depth and thickness of all water, oil and gas formations. PBTD: 3750'

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	287	8 5/8	287	0
		0	4165	4 1/2	4165	1392 1/2 ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

5-23-91: RIGGED UP, FOUND TOP OF SAND AT 3600 ft. 5-24-91: DUMPED 14 SX CEMENT ON TOP OF SAND, SET CIBP AT 2605 ft., DUMPED 2 MORE SX CEMENT, SHOT CASING AT 1392' FT, PULLED 43 JOINTS, RIGGED DOWN & MOVED OFF. 5-24-91: TOP HOLE PLUGGED BY HALLIBURTON., 50 SX CEMENT, 15 SX GEL, 500# NULLS, 150 SX CEMENT, 15 SX GEL, 500# NULLS, PLUG, 60-40 POZ, 6% GEL.
 (If additional description is necessary, use BACK of THIS form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893

Address P O BOX 847 PRATT, KANSAS 67124


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PRATT WELL SERVICE, INC.

STATE OF KANSAS COUNTY OF PRATT, ss.

JUDY BERRY (Employee of ~~Plugging Contractor~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) Pratt Well Service, Inc.



RECEIVED

STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 3rd day of June, 1991

Dorothy M. Ferguson
 Notary Public

JUN 05 1991

My Commission Expires Feb. 6, 1993



GAMMA-GUARD LOG

COMPANY HALLIBURTON OIL PRODUCING COMPANY WELL THOMPSON UNIT # 1 FIELD GERKE NORTH County PRATT State KANS.	COMPANY <u>HALLIBURTON OIL PRODUCING COMPANY</u>			
	WELL <u>THOMPSON UNIT # 1</u>			
	FIELD <u>GERKE NORTH</u>			
	COUNTY <u>PRATT</u> STATE <u>KANSAS</u>			
Location <u>150' E. SW-NE-SE</u>		Other Services: <u>DENSITY</u>		
Sec. <u>1</u>	Twp <u>26S</u>	Rge <u>15W</u>		
Permanent Datum <u>GROUND LEVEL</u> Elev. <u>2022'</u>		Elev.: K.B. <u>2027'</u>		
Log Measured From <u>KELLY BUSHING 5 Ft. Above Perm. Datum</u>		D.F. <u>2024'</u>		
Drilling Measured From <u>KELLY BUSHING</u>		G.L. <u>2022'</u>		
Date	<u>1-25-73</u>	<u>1-25-73</u>		
Run No.	<u>ONE</u>	<u>ONE</u>	<u>RECEIVED</u>	
Depth-Driller	<u>4165'</u>	<u>4165'</u>	<u>STATE CORPORATION COMMISSION</u>	
Depth-Welex	<u>4167'</u>	<u>4167'</u>		
Btm. Log Inter.	<u>4159'</u>	<u>4159'</u>	<u>OCT 01 1973</u>	
Top Log Inter.	<u>0'</u>	<u>287'</u>		
Casing-Driller	<u>@</u>	<u>8-5/8" 287'</u>	<u>CONSERVATION DIVISION</u>	
Casing-Welex			<u>Wichita, Kansas</u>	
Bit Size		<u>7-7/8"</u>		
Type Fluid in Hole		<u>WATER BASE</u>		
		<u>STARCH MUD</u>		
Dens. Visc.	<u>1</u>	<u>9.9 45</u>	<u>1</u>	<u>1</u>
pH Fluid Loss	<u>1 ml</u>	<u>6.3 11.2ml</u>	<u>1 ml</u>	<u>1 ml</u>
Source of Sample		<u>CIRC.</u>		
R ₁₀₀ @ Meas.Temp.	<u>@ °F</u>	<u>.129 @ 50 °F</u>	<u>@ °F</u>	<u>@ °F</u>
R ₅₀₀ @ Meas.Temp.	<u>@ °F</u>	<u>.105 @ 50 °F</u>	<u>@ °F</u>	<u>@ °F</u>
R ₁₀₀₀ @ Meas.Temp.	<u>@ °F</u>	<u>.197 @ 50 °F</u>	<u>@ °F</u>	<u>@ °F</u>
Source R ₁₀₀ R ₁₀₀₀	<u>1</u>	<u>MEAS 1</u>	<u>1</u>	<u>1</u>
R ₁₀₀ @ BHT	<u>@ °F</u>	<u>.058 @ 12 °F</u>	<u>@ °F</u>	<u>@ °F</u>
Time Since Circ.		<u>2.5 HOURS</u>		
Max. Rec. Temp.	<u>°F @</u>	<u>112°F @ 1'D</u>	<u>°F @</u>	<u>°F @</u>
Equip. Location	<u>8521 CT. BEND</u>	<u>1</u>	<u>1</u>	<u>1</u>
Recorded By	<u>ROSENBERG & STUEVE</u>			
Witnessed By	<u>MR. BROOKS</u>			