

RECEIVED

AUG 26 2003

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

KCC WICHITA

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

15-097-1086-02-00

API # Comp. 10-16-62 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR LOTUS OPERATING CO., LLC. KCC LICENSE # 31980
(owner/company name) (operator's)

ADDRESS 914 East Douglas CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 262-1077

LEASE Zimmerman "D" WELL# 1 SEC. 35 T. 27S R. 20W (East/West)

C - NW - NE SPOT LOCATION/QOOQ COUNTY Kiowa

4620 FEET (in exact footage) FROM S (circle one) LINE OF SECTION (NOT Lease Line)

1980 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 350' CEMENTED WITH 300 SACKS

PRODUCTION CASING SIZE 4-1/2" SET AT 4968' CEMENTED WITH 150 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Perfs: 4862-66, 4867-76

ELEVATION 2279/2281 T.D. 4977' PBYD _____ ANHYDRITE DEPTH 1260'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING ACCORDING TO THE RULES AND REGULATIONS OF THE STATE
OF KANSAS.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? _____

If not explain why? Completion Sheet Attached

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Tim Hellman PHONE# 316 262-1077

ADDRESS 914 East Douglas City/State Wichita, Kansas 67202

PLUGGING CONTRACTOR Mike's Testing & Salvage Inc. KCC LICENSE # 31529
(company name) (contractor's)

ADDRESS P.O. Box 467 Chase, Kansas 67524 PHONE # () (316) 938-2943

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) ASAP

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 8-25-03 AUTHORIZED OPERATOR/AGENT: Tim Hellman
(signature)

10-200+ MAP NO. SEC. 35 TWP. 27S RGE. 20W
 STATE Kans COUNTY Kiowa LOC. C NW NE
 OPERATOR Walters Drlg. & Perry B. Ward, Et al FT. FROM LINE
 WELL NO. 1 FARM NAME Zimmerman "D" FT. FROM LINE
 POOL Wildcat ELEV. 2276 E OR 2279 E DF 2281 KD
 FR 8/21/62 SPUD 8/21/62 COMP 10/16/62
 CONT. Walters Drlg., Rig #1 /GEO.
 NAME PRODUCING INTERVAL COMPLETION RECORD TREATMENT RECORD
 FROM - TO PERP. W/HOLES
 Miss 4862-76 52 500 A
 State Pot: Pump
 I. P. OIL/DIST. 35 BO WTR. NW GAS M.C.F.P.D. CHK. HRS. 24
 WC (2 miles So of Fralich (Miss) Pool)
 D A A ()
 SIBP FI TP # FI CPH SIBHP
 GOR. GR. 35.9° PBTD TD 4978
 SIZE DEPTH CASING - CEMENT RECORD SIZE DEPTH W/SAX.
 8 5/8" @ 350 300
 4 1/2" @ 4968 150

RECEIVED
 AUG 26 2003
 KCC WICHITA

OPERATOR Walters Drlg. & Perry B. Ward, Et al		WELL NO. 1 Zimmerman "D"		ELEV. 2281 KB	
SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
KB Tops & Datums:					
Blaine	690	+1591			
Anh	1260	+1021			
Hb	4080		Hb	4080	-1799
BL	4231		BL	4232	-1951
Lans	4241		Lans	4242	-1961
Miss-War	4846		BKc	4644	-2363
			Miss-War	4861	-2580
RTD	4977		Miss-Osage	4939	-2658
DST #1 (Miss-War) 4865-80':		LTD (Osage) 4978:		-2697	
Op 2 hrs, GTS/24", TSTM, R 300' CO (Gray 37 deg) + 480' MCO + 60' MSW, LBHP 1535#/30", IFP 105#, FFP 280#, FBHP 1470#/30"					
DST #2 (Miss) 4880-95' Op 1 hr, WB/31" & died, Flushed 45", WB/7" & died, R 64' M + SSO, LBHP 1535#/30", IFP 50#, FFP 75#, FBHP 1360#/30"					
RTD 4977 (Miss-Osage) Log, 4 1/2" @ 4968' w/150 sx, Perf 16'/4862-66' (Miss-Warsaw) FU 2580' Fluid/14 hrs. = 33 BO + 2 BW, Grv 35.7 deg, Swb 8 1/2 BO/5 hrs, FU 2700" Oil/14					

10-200+ 2 SHEET NO. MAP NO.
 STATE Kans COUNTY Kiowa SEC. 35 TWP. 27S RGE. 20W
 OPERATOR Walters Drlg. & Perry B. Ward, Et al LOC. C NW NE
 WELL NO. 1 FARM NAME Zimmerman "D"

hrs, + 1/2 Gal Wtr. Swb 25 3/4 BO/NT, Swb 1 1/3 BOPH/NW/3 hrs, 500-MA + 112 BLO. Short 23 BL. Perf 36/4867-76 (Miss-Warsaw) Swb 2 1/2 BOPH/3 hrs w/tr Wtr. FU 2420' Fluid/14 hrs. Swb 22 1/2 BO/NT. Swb 12 1/2 BO/8 hrs w/tr Wtr. Swb 108 BNO + 5 1/2 BW/64 hrs. FU 2400' Fluid/14 hrs. Swb 22 BO + 35 GAW/NT. T&R. POP. P 37 BOPD/NW (Gravity 35.7 deg) State Pot: Pump 35 BOPD/NW, Grav. 35.9 deg, Miss 4862-76, 10/9/62.

COMPLETED

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Lotus Operating Company, L.L.C.
914 E Douglas
Wichita, KS 67202-3510

August 26, 2003

Re: ZIMMERMAN D #1
API 15-097-10186-00-00
NWNE 35-27S-20W, 4620 FSL 1980 FEL
KIOWA COUNTY, KANSAS

COPY

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(316) 225-8888

Sincerely



David P. Williams
Production Supervisor