

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

6-2

API NUMBER: 15-155-01,005-00-01

NE-SW-SW SECTION 9 TOWNSHIP 26S RANGE 4W

OPERATOR LICENSE # 5808 990 FEET FROM S SECTION LINE  
OPERATOR W.R.A. Oil Co. 4290 FEET FROM E SECTION LINE  
NAME & P.O. Box 2325  
ADDRESS Hutchinson, KS 67504-2325

LEASE NAME: Back #2 (OWWO)  
COUNTY Reno 131.47  
WELL TOTAL DEPTH: 4045'  
PIPE: \_\_\_\_\_  
SURFACE CASING 13" at 202

ABANDONED OIL WELL  GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Sunflower Well Service Inc.

ADDRESS: P.O. Box 341 Canton, KS 67428 LICENSE: #30280

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 2 MONTH: 6 YR: 1999

PLUGGING PROPOSAL RECEIVED FROM: Bud Davis

COMPANY NAME: Sunflower Well Service Inc. PHONE: 316-628-4723

WERE: Sand to 3983' and top with 4 sxs cement. Shoot pipe off and pull same. Pull pipe to 800' and spot 35 sxs cement. Pull pipe to 400' and spot 35 sxs cement. Pull pipe to 260' and circulate cement to the surface.  
Open hole from 3529' to 4045'.  
4 1/2" casing at 3529'.

PLUGGING PROPOSAL RECEIVED BY: Michael R. Wilson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( ) PART (  ) NONE ( )

COMPLETED: HOUR: 14:45 DAY: 2 MONTH: 6 YEAR: 1999

ACTUAL PLUGGING REPORT: Sanded to 3983' and topped with 4 sxs cement. Built bridge at 3529'. Sanded to 3480' and topped with 2 sxs cement. Shot pipe off at 800' and spotted 35 sxs cement. Pulled pipe to 401' and spotted 35 sxs cement. Pulled pipe to 282' and circulated 180 sxs cement to the surface.

Retrieved 800' of 4 1/2" casing (20 jts.).

REMARKS: Used 60/40 posmix w/4% gel by United - Invoice #5016.

I DID OBSERVE THIS PLUGGING.

Michael R. Wilson  
Michael R. Wilson

FORM CP-2/3  
REV. 3/90

**INVOICED**

DATE 6-10-99

INV. NO. 61045

6-2

AUG 03 1999

RECEIVED  
JUN 08 1999  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
WICHITA, KS