

4-18

2-100708

373  
R

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER: 15-155-20,912-6000

SE SE SW, SECTION 16 TOWNSHIP 26 RANGE 4W

OPERATOR LICENSE # 4656 500 FEET FROM S SECTION LINE  
3000 FEET FROM E SECTION LINE

OPERATOR Davis Petroleum, Inc.  
NAME & RR #1, Box 183B  
ADDRESS Great Bend, KS 67530

LEASE NAME: Holtje #A-2  
COUNTY: Reno  
WELL TOTAL DEPTH: 4117'

133,80

CONDUCTOR PIPE: 4-1/2" @ 4116'  
SURFACE CASING: 8-5/8" @ 304'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD  D&A

OTHER WELL AS HEREINAFTER INDICATED: PERF 4043-49'

PLUGGING CONTRACTOR: Kelso Casing Pulling  
ADDRESS: Box 347, Chase, KS 67524 LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 9:30a DAY: 18 MONTH: 4 YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: \_\_\_\_\_  
COMPANY NAME: \_\_\_\_\_ PHONE: \_\_\_\_\_

WERE: Sand 50' above - 4 sx cmt - shoot & pull pipe to 900'  
- 35 sx - then 360' to surface

PLUGGING PROPOSAL RECEIVED BY: John Sanders

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  )

COMPLETED: HOUR: 12:00p DAY: 18 MONTH: 4 YEAR: 1991

ACTUAL PLUGGING REPORT:  
Sanded to 3975' & dumped 4 sx cmt w/bailer - shot &  
pulled 2600' of 4-1/2" to 900' - spotted 35 sx cmt -  
pulled pipe to 360' - circ 12.5 sx cmt - will top later  
(cmt did not reach top)

RECEIVED  
STATE CORPORATION COMMISSION

REMARKS: Allied #1724 60/40 6% gel

APR 29 1991

I DID OBSERVE THIS PLUGGING.

J. L. Sanders  
J. L. Sanders (AGENT)

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE 5-7-91

INV. NO. 31769

FORM CP-2/3  
REV. 3/90

DW