

4-23

2 100586

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 155-20,943 ~~6000~~

SW NE NW, SEC. 21, T. 26 S, R. 4W W/E  
\_\_\_\_\_ feet from S section line  
\_\_\_\_\_ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # \_\_\_\_\_ 5120

Lease Name Reibenspies Well # 2

Operator: Range Oil Co., Inc.

County Reno 131.63

Name & Address 1120 KSB Bld, 125 N. Market

Well Total Depth 4050 feet

Wichita, KS 67202

Conductor Pipe: Size 4-1/2 feet 4049

Surface Casing: Size 8-5/8 feet 321

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated Perf 4034-4039'

Plugging Contractor B&S Well Service License Number 6013

Address Box 837, Winfield, KS 67156

Company to plug at: Hour: 1:00 Day: 23 Month: 4 Year: 19 90

Plugging proposal received from Randy/Bobby

(company name) B&S Well Service (phone) 316-221-2030

were: Bridge at 4000' w/5 sx of cement - shoot & pull pipe - bridge at 390' & circ to surface.

Plugging Proposal Received by Sanders  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5:00 Day: 23 Month: 4 Year: 19 90

ACTUAL PLUGGING REPORT Sand to 3980' & dump w/bailer 5 sx of cmt - shot & pulled

4-1/2" to 900' & spotted 35 sx cmt - pulled pipe to 400' & circ to surface

w/180 sx cmt - pulled rest of pipe out & topped off.

STATE CORPORATION COMMISSION  
RECEIVED

MAY 21 1990

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: United #595 60/40 2% gel

INVOICED

DATE 6-6-90 (did ~~XXXXXX~~ observe this plugging.)

INVOICE NO. 28335

Signed J.L. Sanders  
(TECHNICIAN)