

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

1-26

01698-0000

API NUMBER: 15-155-49001

Nw Ne Nw, SECTION 29 TOWNSHIP 26 RANGE 4 ^W

OPERATOR LICENSE # 30146
OPERATOR Mach Petroleum Inc.
NAME & Po Box 35583
ADDRESS Tulsa, Ok 74153

4950 FEET FROM S SECTION LINE
3630 FEET FROM E SECTION LINE

LEASE NAME: Guebbel 4
COUNTY: RC
WELL TOTAL DEPTH: 4032 ^{131.04}
PIPE: 5 1/2" 4015
SURFACE CASING: 8 5/8" 224'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Clark Corp.
ADDRESS: Po Box 187 Medicine Lodge Ks. LICENSE: 5105

COMPANY TO PLUG AT: HOUR: 12:00 DAY: 26 MONTH: 1 YR: 1999

PLUGGING PROPOSAL RECEIVED FROM: Alan Vratil
COMPANY NAME: Clark Corp. PHONE: 316-886-5665
WERE: Sand to 3910' & 5 Sk
35 Sk 700'
275' To Surface

RECEIVED
KANSAS CORPORATION COMMISSION
2-3-99
FEB 03 1999

PLUGGING PROPOSAL RECEIVED BY: JL

CONSERVATION DIVISION
WICHITA, KS

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 5:00 DAY: 26 MONTH: 1 YEAR: 1999

ACTUAL PLUGGING REPORT: Sanded bottom to 3910 & 5 Sk. Shot 5 1/2" Casing
off at 3200' Pulled all the Casing, rantubing back to 700'
Pumped 35 Sks Pulled to 275' Pumped 165 Sks Cement would not
Circulate; Sent for more cement; Pulled tubing out of the hole
Ran back in with wiper plug on tubing Pumped 125 Sk Cir to
Surface

REMARKS: Allied # 7637 60/40 4%

INVOICED

DATE 2-10-99
REV. NO. 60629

I DID OBSERVE THIS PLUGGING.

Jack Luthi
JACK LUTHI