

9-17

2-

RECEIVED  
KANSAS CORPORATION COMMISSION

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

OCT 01 1993

CONSERVATION DIVISION  
WICHITA, KS

API NUMBER: 15-155-21,149-0000

SE SE SE, SECTION 2 TOWNSHIP 26 RANGE 6W

OPERATOR LICENSE # 5808

330 FEET FROM S SECTION LINE  
330 FEET FROM E SECTION LINE

OPERATOR W R ALLAM  
NAME & BOX 2325  
ADDRESS HUTCHINSON, KS 67504

LEASE NAME: HORSCH-KREHBIEL #1  
COUNTY: RENO  
WELL TOTAL DEPTH: 4036' 131.17

CONDUCTOR PIPE: \_\_\_\_\_

SURFACE CASING: 8-5/8" @ 235'

ABANDONED OIL WELL  GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SMD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: SUNFLOWER WELL SERVICE  
ADDRESS: BOX 341, CANTON, KS LICENSE: 30280

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 17 MONTH: 9 YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: DAVE WERTZ  
COMPANY NAME: SAME PHONE: \_\_\_\_\_  
WERE: SAND TO 3939; & 5 SX - 35 SX @ 950' - 35 SX @ 450' -  
280' TO SURFACE.

PLUGGING PROPOSAL RECEIVED BY: DAVE WERTZ

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART ( \_\_\_\_\_ ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 4:00 DAY: 17 MONTH: 9 YEAR: 1993

ACTUAL PLUGGING REPORT:  
SANDED BOTTOM TO 3939' & 5 SX COMMON - SHOT 5-1/2"  
CSG OFF @ 1683' & PULLED TO 950' - PUMPED 35 SX -  
PULLED TO 450' & PUMPED 35 SX - PULLED TO 2.80' & CIRC  
CMT TO SURF.

REMARKS: UNITED #4384 60/40 4%

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 10-4-93

131  
\_\_\_\_\_  
Jack Luthi (AGENT)

INV. NO. 38837

FORM CP-2/3  
REV. 3/90

9-17