

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-20175-00-00
Spot: SENENENW Sec/Twnshp/Rge: 10-26S-13W
4871 feet from S Section Line, 2859 feet from E Section Line
Lease Name: GRIFFITH A TWIN Well #: 1
County: PRATT Total Vertical Depth: 4215 feet

Operator License No.: 34289
Op Name: ADAMS AFFILIATES, INC.
Address: 1437 S. BOULDER, STE 930
TULSA, OK 74119

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4090		WITH 2 SX CMT
PROD	4.5	4215	0	WITH 125 SX CMT
SURF	8.625	440		WITH 435 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 08/20/2015 8:30 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: JENNIFER SEXTON Company: ADAMS AFFILIATES Phone: (918) 691-4905

Proposed Plugging Method: SET CIBP 50' ABOVE PERFS & 2 SX CMT. PERFORATE AT 780'. PUMP 10 SX GEL THEN CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/24/2015 12:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4090' & PUT 2 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. PERFORATE AT 780'. PUMP DOWN 4 1/2" CASING WITH 10 SX GEL & 265 SX CMT. CMT CIRCULATED. STAGED CMT WITH ANOTHER 20 SX CMT. WELL ON VACUUM. SHUT WELL IN. 8/21/15: RUN IN WITH TAPE TO 330'. DID NOT FIND TOP OF CMT. (HAD NOTHING LONGER TO RUN IN). FOUND TOP OF FLUID AT APPROXIMATELY 240'-260'. 8/24/15: FOUND TOC INSIDE 4 1/2" CASING AT 348'. RUN BOND LOG & FOUND NO CMT ON BACKSIDE OF 4 1/2" CASING. PERFORATE AT 300'. PUMPED DOWN 4 1/2" CASING WITH 100 SX CMT. CMT CIRCULATED TO SURFACE IN 4 1/2" X 8 5/8" ANNULUS & FILLING 4 1/2" CASING TO SURFACE WITH CMT.

Perfs:

Top	Bot	Thru	Comments
4135	4145		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

9/16/15 CKM

District: 01

Signed Steve Pfeifer
SA (TECHNICIAN)

RECEIVED
SEP - 8 2015
KCC DODGE CITY