

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-20994-00-01
Spot: NESE Sec/Twnshp/Rge: 12-20S-21W
1906 feet from S Section Line, 660 feet from E Section Line
Lease Name: HINNEGARDT Well #: 2
County: NESS Total Vertical Depth: 1087 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	2.875	820		CEMENTED TO SURFACE
PROD	4.5	1087	0	WITH 250 SX CMT
SURF	8.625	255		WITH 170 SX CMT

Well Type: SWD UIC Docket No: D20118.0 Date/Time to Plug: 09/02/2015 9:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (785) 398-2270

Proposed Plugging Method: TIE ONTO TBG & PUMP 200# HULLS & CMT UNTIL SHUTS OFF. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/02/2015 11:00 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

TIED ONTO LINER & PUMPED 70 SX CMT & 200# HULLS. PRESSURED TO 800#. TIED ONTO BACKSIDE & PUMPED 10 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
870	1020		

KCC WICHITA
SEP 14 2015
RECEIVED

Remarks: **COMPLIANCE ISSUE: NOV TA LTR** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

9/21/15 CKM

District: 01

Signed Michael Maier
MA (TECHNICIAN)

RECEIVED
SEP - 8 2015
KCC DODGE CITY MP

UIC ✓