

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-145-21395-00-00
Spot: NESWSW Sec/Twnshp/Rge: 20-20S-19W
1200 feet from S Section Line, 1052 feet from W Section Line
Lease Name: BARTONEK Well #: 20-13-2
County: PAWNEE Total Vertical Depth: 4325 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4210		
PROD	5.5	4323	0	WITH 125 SX CMT
SURF	8.625	469		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/10/2015 10:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed Plugging Method: CIBP @ 4140' WITH 2 SX CMT OR PUMP 25 SX CMT WITH 100# HULLS & PRESSURE UP. PERFORATE AT 1390' SQUEEZE 50 SX CMT. LET SET UP & TAG. PERFORATE AT 510' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: NONE
Date/Time Plugging Completed: 09/10/2015 1:50 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

PUMP 25 SX CMT & 100# HULLS TO DISPLACE TO 4050'. PERFORATE AT 1354' WITH 80 SX CMT. TOC AT 1300'. PERFORATE AT 519' WITH 160 SX CMT TO 0'.

Perfs:

Top	Bot	Thru	Comments
4192	4197		

Received
KANSAS CORPORATION COMMISSION
SEP 17 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY COPELAND

Plugged through: CSG

9/21/2015 CKM

District: 01

Signed _____
(TECHNICIAN)

RECEIVED
SEP 11 2015
KCC DODGE CITY