

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-193-20568-00-00
Spot: SWSESE Sec/Twnshp/Rge: 16-10S-31W
339 feet from S Section Line, 1129 feet from E Section Line
Lease Name: FLIPSE Well #: 1
County: THOMAS Total Vertical Depth: 2569 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2569		430 SX
SURF	8.625	332		200 SX

Well Type: SWD UIC Docket No: D26398.0 Date/Time to Plug: 08/20/2015 10:30 AM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO LLC Phone: (316) 772-8649

Proposed Plugging Method: 8 5/8" surface casing set at 332' w/200 sx cement. 4 1/2" production casing set at 2569' w/430 sx cement. TD 2569', Perforations: 2313 - 2325'. Top down plug.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/20/2015 2:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs:

Connected to 4 1/2" production casing and pumped 50 sx cement w/no hulls, followed by 130 sx cement w/350 # hulls. No pressure. Cement fell in 4 1/2" casing. WOC for 2 hours. Connected to 8 5/8" surface casing and pumped 15 sx cement. Pressured to 350 psi. Topped off 4 1/2" casing with 25 sx cement. 4 1/2" casing full of cement. Plug complete.
GPS: 39.17770N -100.78070W

Remarks: QUALITY WELL SERVICE AND CEMENTING TICKET # 6367

Plugged through: CSG

9/21/15 CKM

District: 04

Signed Darrel Dipman
(TECHNICIAN) CM

KCC WICHITA
SEP 04 2015
RECEIVED

AUG 5 2015

AUG 25 2015