

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-22568-00-00
Spot: N2SWNWSW Sec/Twnshp/Rge: 31-17S-30W
1750 feet from S Section Line, 330 feet from W Section Line
Lease Name: ARAPAHOE Well #: 31-1
County: LANE Total Vertical Depth: 4700 feet

Operator License No.: 34917
Op Name: BICKLE ENERGIES LLC
Address: 2052 250TH AVE
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	347		WITH 180 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/07/2015 11:30 PM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: BILL SANDERS Company: SOUTHWIND DRILLING, INC. Phone: (620) 564-3800

Proposed Plugging Method: 1ST PLUG AT 2275' WITH 50 SX CMT. 2ND PLUG AT 1550' WITH 80 SX CMT. 3RD PLUG AT 750' WITH 50 SX CMT. 4TH PLUG AT 380' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: LARRY HARRIS Witness Type: NONE
Date/Time Plugging Completed: 08/08/2015 1:30 AM KCC Agent: LARRY HARRIS

Actual Plugging Report:

Perfs:

1ST PLUG AT 2275' WITH 50 SX CMT. 2ND PLUG AT 1550' WITH 80 SX CMT. 3RD PLUG AT 750' WITH 50 SX CMT. 4TH PLUG AT 380' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY 1/4# FLO SEAL BY QUALITY OIL WELL.

Plugged through: DP

9/21/15 ckm

District: 01

Signed Larry Harris PERT II
(TECHNICIAN)

RECEIVED
AUG 26 2015
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION
SEP 03 2015
CONSERVATION DIVISION
WICHITA, KS