

API Well Number: 15-125-02856-0000

Spot: NE/NE/SE Sec 2 Twp 35 S Rng 16 ☒ E / ☐ W  
2398 2398 Feet from ☐ N / ☒ S Line of Section  
645 645 Feet from ☒ E / ☐ W Line of Section

GPS: Lat: 37.028260 Long: 95.622390 Date: 7/30/15

Lease Name: ACME Well #: ACME 01

County: Montgomery Total Vertical Depth: 385 feet

**Kansas Corporation Commission**  
**District Plugging Report**

Operator License No: 101 String Size Depth Pulled Comments  
Op Name: KANSAS CORPORATION COMMISSION SURF - Casing 6.250  
Address 1: 226 N MAIN STE 220  
Address 2:  
City: WICHITA  
State: KS Zip Code: 67202 -

Well Type: OG - Oil & Gas (oil) UIC Docket No.: Date/Time to Plug: 8/3/15 /  
Plug Co License No.: 33749 Plug Co. Name: KWS  
Proposal Rcvd from: MIKE KEPLEY Company Name: KWS Phone: (620) 431-9212

Proposed Plugging Report: CLEAN OUT WELLS TO BOTTOM. PUMP FULL OF PORTLAND CEMENT, INSIDE AND OUTSIDE OF CASING. IF CEMENT IS PRESENT IN THE ANNULUS, CASING SHOULD BE PERFORATED IN AT LEAST 2 INTERVALS, UNLESS WELL IS DOCUMENTED AS ALT. 2 COMPLETION.

Plugging Proposal Received By: TOM BILYEU Witness Type: COMP - Complete 100%  
Date/Time Plugging Completed: 8/3/15 / KCC Agent: TONY ANDERSON/TOM BILYEU

Actual Plugging Report: Perfs: Top Bottom Thru  
WELL WAS DUG OUT BY MULLER CONSTRUCTION WHILE PREPARING BUILDING PAD. RAN SWEDGE TO 370' AND RAN COLLAR LOCATOR. WASHED TO 385' AND STARTED PUMPING CEMENT. FRESH WATER WAS MIXING WITH CEMENT, WE HAD TO STOP FOR 3 HOURS TO LET CEMENT TO SEAL OFF WATER. RESUMED PUMPING AND GOT GOOD CEMENT TO SURFACE. 182 SACKS OF CEMENT WERE USED. SUCKED THE PIT OUT AND MULLER CONSTRUCTION DID THE RESTORATION.

Remarks: CONTRACT#38595;CONTROL#20160007-001; GPS BY TOM NAD 83.

Plugged Thru: TBG - Tubing Received Plugged Due to Compliance Issue: ☐ Yes ☐ No

District: 03 SEP 04 2015 Tony Anderson (Technician)  
CONSERVATION DIVISION WICHITA, KS Form: District Plugging Report -