

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-20930-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 9-29S-6W
1190 feet from S Section Line, 4980 feet from E Section Line
Lease Name: KLAVER Well #: 6
County: KINGMAN Total Vertical Depth: 4550 feet

Operator License No.: 5348
Op Name: CAMPBELL, ROBERT E.
Address: 260 N ROCK RD STE 110
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4549	2250	325 SX
SURF	8.625	280		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/31/2015 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (316) 685-6001

Proposed Plugging Method: SAND BACK TO 4050 & 2 SKS. 35 SXS @ 1000', 35 SXS @ 550'. CIRCUALTE 330'.

Plugging Proposal Received By: B. J. HOPE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/02/2015 2:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 4050' & CAPPED WITH 2 SKS CEMENT. RECOVERED CASING FROM 2250' & PULLED TO 1000' WHERE 35 SXS OF CEMENT WAS SPOTTED. PULLED CASING TO 550' WHERE 35 SXS OF CEMENT WAS SPOTTED. PULLED CASING TO 330' & CIRCUALTED CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4484	4471	CSG	
4471	4484	CSG	
4106	4097	CSG	
4097	4106	CSG	


KCC WICHITA
SEP 15 2015
RECEIVED

Remarks: QUALITY WELL SERVICE. COMMON CEMENT 3% CACL. DENIED TA

Plugged through: CSG

District: 02

Signed _____

 9/22/15 CJKM

(TECHNICIAN)