

9-24

2-100637

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

15-155-02413-00-00
API NUMBER: 2/13/53

NE SE NW, SECTION 3 TOWNSHIP 26 RANGE 4W

OPERATOR LICENSE # 4767

FEET FROM S SECTION LINE

FEET FROM E SECTION LINE

OPERATOR Ritchie Exploration, Inc.

NAME & 125 N. Market St., #1000

ADDRESS Wichita, KS 67202

LEASE NAME: Prough "P" #1

COUNTY: Reno

133.34

WELL TOTAL DEPTH: 4103' PB 3300'

PIPE: 5-1/2" @ 4097'/325 sx

SURFACE CASING: 8-5/8" @ 332'/250 sx

ABANDONED OIL WELL GAS WELL INPUT WELL SMD D&A

OTHER WELL AS HEREINAFTER INDICATED: Perf 3294-88', 3261-47', 3222-18', 3189-02', 3157-60', 3120-26', 3017-23'

PLUGGING CONTRACTOR: Kelso Casing Pulling, Inc.

ADDRESS: Box 347, Chase, KS 67524

LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 3:00p DAY: 24 MONTH: 9 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Bill

COMPANY NAME: Kelso Casing Pulling, Inc.

PHONE: 316-938-2943

WERE: Sand to 2965' w/5 sx cmt - 35 sx at 650' - 35 sx at 430' & circ from 390'

PLUGGING PROPOSAL RECEIVED BY: Jack Luthi

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 4:00 DAY: 24 MONTH: 9 YEAR: 1990

ACTUAL PLUGGING REPORT:

Sanded to 2965' & dumped 5 sx of cmt w/bailer - shot & pulled 2520' of 5-1/2" to 650' - pumped 35 sx cmt mixed w/1 sx hulls - pulled pipe to 430' & pumped 35 sx cmt - mixed 1 hulls - pulled pipe to 390' & circ cmt to surf - topped off.

REMARKS: Allied #6023 60/40 4% gel

INVOICED

DID YOU OBSERVE THIS PLUGGING?

DATE 10-8-90 OCT 1 1990

REV. NO. 29574 CONSERVATION DIVISION
Wichita, Kansas

J. L. Sanders (AGENT)