

5-16 15-151-00370-00-01 228P
API NUMBER 19- NA

1 040537

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SE NW, SEC. 16, T. 26 S, R. 11 W/E
2970 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5027
Operator: J.A. Allison
Name & Address: 300 W. Douglas, Suite 305
Wichita, KS 67202

Lease Name Shriver Well # 2
County Pratt 141.05
Well Total Depth 4340 feet
Conductor Pipe: Size feet
Surface Casing: Size 10 3/4 feet 385

Abandoned Oil Well Gas Well Input Well SWD Well O&A
Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:45 a.m. Day: 16 Month: 5 Year: 19 91

Plugging proposal received from Millard Kelso
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

Perfs at 4041-50, 3897-3900, 3866-71, 3773-78, 3614-18"
were: 5 1/2" at 4146' w/150 sx cement.
1st plug sand over perfs to 3575' with 5 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,
and 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
6-4-91
JUN 04 1991
(TECHNICIAN) Dan Goodrow
Wichita, Kansas

Plugging Proposal Received by Dan Goodrow

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11 a.m. Day: 16 Month: 5 Year: 19 91

ACTUAL PLUGGING REPORT 5/10/91- Attempt to plug: pumped 50 lbs. hulls down 10 3/4" surface pipe. Surface pipe circulated on backside. Shut down & waited on rig to move onto well to plug through tubing.

1st plug sanded back to 3560' and dumped 5 sx cement on top of sand through bailer, Bayse Well Service on hole to run tubing: 2nd plug at 660' with 50 sx cement,

3rd plug at 420' with 70 sx cement, 4th plug at 40' with 20 sx cement. Gel spacer between plugs. (12 sx of gel)

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1957' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-11-91
INV. NO. 32077

Signed [Signature] (TECHNICIAN)