

To: 1 041157  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 151-20,342 -00-00  
200' NE of  
SW NE SE, SEC. 1, T 26 S, R 15 W/E  
1750 feet from S section line  
890 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5893  
Operator: Pratt Well Service Inc.  
Name & Address: P.O. Box 847  
Pratt, KS 67124-0847

Lease Name Thompson Well # 2  
County Pratt 119.43  
Well Total Depth 3675 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 337

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service Inc. License Number 5893  
Address P.O. Box 847, Pratt, KS 67124-0847

Company to plug at: Hour: 9:30 a.m. Day: 20 Month: 3 Year: 1996

Plugging proposal received from Aaron Hammerschmitt  
(company name) Pratt Well Service Inc. (phone) 316-672-2531

Work: 4 1/2" at 3675' w/550 sx cement, PBD 2815', Perfs at 2711-13'  
1st plug sand back to 2661' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 6 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durran (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None

Operations Completed: Hour: 10 a.m. Day: 20 Month: 3 Year: 1996

ACTUAL PLUGGING REPORT 1st plug sanded back to 2261' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 6 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 300 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1768' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed *Stephan J. Geyer* (TECHNICIAN)

DATE MAR 28 1996

INV. NO. 45160

3-20

RECEIVED  
KANSAS CORP COM  
MAR 28 1996

3-26-96