

To: 1 120570  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WYCHITA, KANSAS 67202

API NUMBER 15- (no Docket #) 15-151-20,206-00,00  
150' NE of  
SE NE SE, SEC. 1, T. 26 S, R 15 W/E  
1750 feet from S section line  
380 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5893  
Operator: Pratt Well Service  
Name & Address P.O. Box 847  
Pratt, KS 67124-0847

Lease Name Thompson Well # 1 SWD  
County Pratt 135.39  
Well Total Depth 4166 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 287

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well  D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service License Number 5893  
Address P.O. Box 847, Pratt, KS 67124-0847

Company to plug at: Hour: 4 p.m. Day: 24 Month: 5 Year: 19 91

Plugging proposal received from Kenneth Gates  
(company name) Pratt Well Service (phone) 316-672-5901

were: 4 1/2" at 4165', TOC 1900', Perfs at 3676-79 & 2717-13'  
1st plug sand back to 3750' with 4 sx cement on top, 2nd plug set CIBP at 2600' w/2 sx cement  
3rd plug pump in 8 5/8" surface casing with 350 lbs. hulls, 5 sx gel, 50 sx cement, 10  
sx gel, 150 lbs. hulls and 150 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

6-7-91 JUN 7 1991

Plugging Proposal Received by Duane Rankin  
(TECHNICIAN) CONSERVATION DIVISION  
Wichita, Kansas

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5 p.m. Day: 24 Month: 5 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 3600' and dumped 4 sx cement  
on top of sand through bailer,  
2nd plug set CIBP at 2600' with 2 sx cement on top,  
3rd plug pumped into 8 5/8" surface casing with 350 lbs. hulls, 5 sx gel, 50 sx cement,  
10 sx gel, 150 lbs. hulls and 150 sx cement.  
Pumping pressure 0-400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 1392' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

Signed Duane Rankin  
(TECHNICIAN)

DATE 6-18-91  
INV. NO. 32170