

1041380

TO: STATE CORPORATION COMMISSION

API NUMBER 15-151-20,066-00-00
NE LOT 2 SEC. 1, T 26 S, R 15 W

CONSERVATION DIVISION - PLUGGING SECTION 2640 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME ELLIS WELL # 2

TECHNICIAN'S PLUGGING REPORT

COUNTY PRATT 144.04

OPERATOR LICENSE # 5552

WELL TOTAL DEPTH 4432 FEET

OPERATOR: GORE OIL COMPANY

PRODUCTION CSG: SIZE 4 1/2" @ 4431' WITH 200 SX

NAME AND PO BOX 2757

SURFACE CASING: SIZE 8 5/8" @ 318' WITH 320 SX

ADDRESS WICHITA, KS 67201-2757

ABANDONED OIL WELL GAS WELL INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 10:00 AM DAY: 23 MONTH: 12 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM GARY REH WITH GORE OIL

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 4354-78, 4246-54, 4079-83, 4052-58, 4000-02, 3960-72, 3847-55, 3821-26

4008-10, CIBP @ 4320'.

SANDED BACK TO 3750' AND PUT 4 SX CEMENT ON TOP OF SAND BRIDGE THROUGH BAILER. PUMP DOWN

8 5/8" SURFACE PIPE WITH 300# HULLS, 10 SX GEL, 50 SX CEMENT, 10 SX GEL, 100# HULLS, 8 5/8"

WIPER PLUG, AND 125 SX CEMENT. MAXIMUM PRESSURE AT 900#. SHUT IN WITH 600#.

INVOICED

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

DATE 11/10/00

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 10:45 AM DAY: 23 MONTH: 12 YEAR: 1999

ACTUAL PLUGGING REPORT

SANDED BACK TO 3750' AND PUT 4 SX CEMENT ON TOP OF SAND BRIDGE THROUGH BAILER. PUMP DOWN

8 5/8" SURFACE PIPE WITH 300# HULLS, 10 SX GEL, 50 SX CEMENT, 10 SX GEL, 100# HULLS, 8 5/8"

WIPER PLUG, AND 125 SX CEMENT. MAXIMUM PRESSURE AT 900#. SHUT IN WITH 600#.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2130' OF 4 1/2" CASING
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Stephen J. Pfeifer (TECHNICIAN) FORM CONSERVATION DIVISION
Wichita, Kansas RECEIVED JAN 05 2000