

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-22470-00-00  
Spot: NWNWNE Sec/Twnshp/Rge: 6-35S-13W  
330 feet from N Section Line, 2000 feet from E Section Line  
Lease Name: MORROW A Well #: 2-6  
County: BARBER Total Vertical Depth: 5521 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, LLC  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4800		WITH 2 SX CMT
PROD	5.5	5521	2534	WITH 110 SX CMT
SURF	8.625	470		WITH 250 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/01/2015 1:00 PM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 4800' WITH 2 SX CMT. PLUG AT 700' WITH 15 SX GEL & 50 SX CMT. PLUG AT 500' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: LARRY HARRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/01/2015 4:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4800' WITH 2 SX CMT. 1ST PLUG AT 709' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 498' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 53 SX CMT. CIRCULATED APPROXIMATELY 30 SX CMT TO PIT.

Perfs:

Top	Bot	Thru	Comments
4848	4920		

KCC WICHITA  
SEP 08 2015  
RECEIVED

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED  
SEP - 3 2015  
KCC DODGE CITY