

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-30065-00-00
Spot: SENE SW Sec/Twnshp/Rge: 31-34S-13W
1650 feet from S Section Line, 2310 feet from W Section Line
Lease Name: F W WOLGAMOTT Well #: 1-31
County: BARBER Total Vertical Depth: 4932 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4800		WITH 2 SX CMT
PROD	5.5	4932	1680	WITH 425 SX CMT
SURF	8.625	365		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/21/2015 1:30 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 682-9100

Proposed Plugging Method: CIBP @ 4800' WITH 2 SX CMT. PLUG AT 700' WITH 15 SX GEL & 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/21/2015 2:40 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

CIBP @ 4800' WITH 2 SX CMT. 1ST PLUG AT 695' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 406' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 8/25/15: PLUG DROPPED 200'. TOPPED OFF WITH 70 SX CMT. HOLE STAYING FULL.

Perfs:

Top	Bot	Thru	Comments
4854	4885		

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
AUG 26 2015
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION
SEP 03 2015
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3