

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-055-00343-00-00  
Spot: SW Sec/Twnshp/Rge: 17-23S-31W  
1286 feet from S Section Line, 4027 feet from E Section Line  
Lease Name: SOMERS Well #: 1-17  
County: FINNEY Total Vertical Depth: 2721 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, LLC  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2718	0	WITH 300 SX CMT
SURF	8.625	293		WITH 225 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/27/2015 10:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: BUD NEFF Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/27/2015 3:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 100 SX CMT & 200# HULLS TO 2666'. DISPLACE WITH WATER TO 1640'.  
PRESSURE TEST CASING TO 600#. HOLDING. RUN CBL FROM 1320' TO 100'. TOP  
OF CMT IN ANNULUS IS 630'. USABLE WATER IS COVERED. PERFORATE AT 320'.  
RUN TBG TO 1296' & CIRCULATE CMT TO SURFACE UP THE 4 1/2" CASING AND  
THROUGH THE PERFS AT 320' UP THE 4 1/2" X 8 5/8" ANNULUS TO SURFACE  
USING 200 SX CMT. TOP OFF WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2656	2666		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed Ken Jehlik  
SA (TECHNICIAN)

RECEIVED  
SEP - 3 2015  
KCC DODGE CITY

Received  
KANSAS CORPORATION COMMISSION

Form CP-2/3

SEP 18 2015  
CONSERVATION DIVISION  
WICHITA, KS