

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-20268-00-00
Spot: SENW Sec/Twnshp/Rge: 29-21S-40W
3318 feet from S Section Line, 3324 feet from E Section Line
Lease Name: GRILLIOT Well #: 3
County: HAMILTON Total Vertical Depth: 2900 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2869	0	WITH 450 SX CMT
SURF	8.625	353		WITH 150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/31/2015 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 200# HULLS & 175 SX CMT DOWN 4 1/2" CASING. CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/31/2015 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 4 1/2" CASING WITH CMT FROM 2773' TO 0' USING 200# HULLS & 195 SX CMT. PRESSURE TO 500#. HOLDING. PUMP 25 SX CMT DOWN THE ANNULUS TO 300#. HOLDING.

Perfs:


Top	Bot	Thru	Comments
2769	2773		

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed


(TECHNICIAN)

RECEIVED
SEP - 3 2015
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

SEP 18 2015

CONSERVATION DIVISION
WICHITA, KS