

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-099-24593-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 10-32S-18E
2227 feet from S Section Line, 4790 feet from E Section Line
Lease Name: PETERSON Well #: 12-10
County: LABETTE Total Vertical Depth: 1015 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD | 5.5 | 1011 | | 125 SX |
| SURF | 8.625 | 21 | | 4 SX |

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 09/02/2015 12:00 AM
Plug Co. License No.: 5150 Plug Co. Name: COLT ENERGY INC
Proposal Rcvd. from: RICK RICE/COLT ENERGY Company: _____ Phone: (620) 380-1236

Proposed Plugging Method: 2" tubing to TD, gel up hole, 50' cement plug @ bottom, 50' cement plug @ 500', cement from 250' to surface, pull 2" tubing out of hole, top well off with cement.

Plugging Proposal Received By: _____ WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/02/2015 12:00 AM KCC Agent: RUSSELL HINE

Actual Plugging Report:

A MIX OF BENTONITE AND WATER WAS PUMPED TO GEL THE WELL UP, THIS WAS FOLLOWED BY A 50' CEMENT PLUG PLACED ON BOTTOM, PULLED TUBING TO 500' WHERE ANOTHER 50' CEMENT PLUG WAS PLACED, THE TUBING WAS PULLED TO 250', CEMENT WAS PUMPED IN AND CIRCULATED TO THE SURFACE. THE REST OF THE TUBING WAS PULLED, AND THE PRODUCTION CASING WAS TOPPED OFF WITH CEMENT. 65 +/- SKS OF PORTLAND CEMENT WERE USED

Perfs: _____

KCC WICHITA
SEP 14 2015
RECEIVED

RECEIVED
KCC DIST # 3
SEP 10 2015
CHANUTE, KS

R.H.

Remarks:

Plugged through: TBG

District: 03

Signed Russell Hine
(TECHNICIAN)