

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-21062-00-01  
Spot: NWSWSE Sec/Twnshp/Rge: 17-26S-8E  
963 feet from S Section Line, 2135 feet from E Section Line  
Lease Name: DUNNE B Well #: 3  
County: BUTLER Total Vertical Depth: 2775 feet

Operator License No.: 30931  
Op Name: DAYSTAR PETROLEUM, INC.  
Address: 522 N. MAIN ST PO BOX 560  
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2774		165 SX
SURF	7	165		60 SX

Well Type: EOR UIC Docket No: E19808.1 Date/Time to Plug: 08/15/2015 12:00 AM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: JASON BRANCH Company: DAYSTAR PETROLEUM Phone: (620) 583-2932

Proposed Plugging Method: Per KCC instructions

Plugging Proposal Received By: DUANE KRUEGER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/02/2015 3:00 AM KCC Agent: JONATHAN HILL

Actual Plugging Report:

1) PERFORATED WITH 3 SHOTS AT 250'. 2) RAN IN HOLE W/TUBING TO 2585' AND HIT UNKNOWN OBSTRUCTION. ABLE TO WASH DOWN FURTHER TO 2616'. 3) PUMPED 30 SKS OF 60/40 4% CEMENT WITH 3% CACL, PULLED UP TUBING TO 1800'. 4) LET CEMENT SIT FOR APPROX 1.5 HRS, RAN IN HOLE W/WIRELINE AND TAGGED CEMENT AT 2213'. 5) PUMPED 500 LBS OF GEL TO FILL HOLE FROM 1800' TO 300'. 6) PULLED TUBING OUT, TIED INTO 4.5" CASING AND PUMPED 55 SKS CEMENT W/ TRACER DYE. CEMENT CIRUCALTED TO SURFACE UP BACKSIDE.

Perfs:

Top	Bot	Thru	Comments
2701	2754		CSG
2564	2596		CSG

KCC WICHITA  
SEP 15 2015  
RECEIVED

Remarks: CEMENTING COMPLETED BY HURRICANE SERVICES, INC. TICKET #:100613. PLUGGED DUE TO FAILED MIT.

Plugged through: TBG

District: 02

Signed [Signature]  
(TECHNICIAN)

[Handwritten mark]

UIC