

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-153-21167-00-00  
Spot: SWNWSNW Sec/Twnshp/Rge: 35-1S-36W  
1820 feet from N Section Line, 1480 feet from W Section Line  
Lease Name: BERNITA A Well #: 1-35  
County: RAWLINS Total Vertical Depth: 4740 feet

Operator License No.: 3180  
Op Name: DEUTSCH, KENT A. DBA DEUTSCH OI  
Address: 8100 E 22ND ST N  
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	307		215 sx

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/02/2015 12:00 AM  
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.  
Proposal Rcvd. from: BILL Company: SOUTHWIND DRILLING, INC. Phone: (620) 617-0706

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB Witness Type: NONE  
Date/Time Plugging Completed: 09/02/2015 4:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

1st plug @3233 w/50 sx  
2nd plug @2461 w/100 sx  
3rd plug @357 w/50 sx  
4th plug @40 w/10 sx  
  
Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: CONSOLIDATED

Plugged through: DP

District: 04

Signed   
(TECHNICIAN) CM

Received  
KANSAS CORPORATION COMMISSION

Form CP-2/3

SEP 11 2015

SEP 18 2015

CONSERVATION DIVISION  
WICHITA, KS