

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-23823-00-00
Spot: SENWSWNE Sec/Twnshp/Rge: 13-30S-14W
1830 feet from N Section Line, 2200 feet from E Section Line
Lease Name: LENKNER "A" Well #: 1-13
County: BARBER Total Vertical Depth: 4900 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	13.375	312		WITH 300 SX CMT
PROD	5.5	4900	2240	WITH 455 SX CMT
SURF	8.625	952		WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/21/2015 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 20-30 SX CMT WITH 200# HULLS. PLUG AT 1000' WITH 50 SX CMT. PLUG AT 500' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/21/2015 1:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PUMPED DOWN 5 1/2" CASING WITH 200# HULLS & 30 SX CMT. SHUT IN AT 1000#. TAGGED TOC @ 3750'. 1ST PLUG AT 1000' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 500' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4645	4649		
4644	4647		
4008	4014		

KCC WICHITA
SEP 14 2015
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL.

Plugged through: CSG

District: 01

Signed Steve Pfeifer
SA (TECHNICIAN)

RECEIVED
SEP - 8 2015
KCC DODGE CITY